



U.S. Department
of Transportation
**Federal Highway
Administration**

Eastern District Federal Division

1000 North Glebe Road
Arlington, Virginia 22201

APR 19 1985

In Reply Refer To:
HPC-15

STAT

[Redacted]
New Building Project Office
Central Intelligence Agency
P.O. Box 20505
Washington, D.C. 20505

STAT

Dear [Redacted]

Enclosed for your review and comments is one copy each of the plans, Special Contract Requirements, and Engineer's Estimate for George Washington Memorial Parkway (GWMP) Project 1A58.

The project consists of pavement widening and other work for the acceleration lane from the CIA-FHWA Federal Area at Langley to northbound GWMP in Fairfax County, Virginia. It is expected to allow 40 calendar days for the contract work.

The estimated cost of the project is \$960,000 including contract, engineering, and administration cost. Please forward the funds at your earliest convenience.

We expect to negotiate this project under the Small Business Administration's 8(a) Program.

Your comments are requested by May 17, 1985.

Sincerely yours,

Roy M. Crawford
Acting Division Engineer

Enclosures

FEDERAL HIGHWAY ADMINISTRATION
 EASTERN DIRECT FEDERAL DIVISION
 ARLINGTON, VIRGINIA
 TABULATION OF BIDS

IFB DTFH 71-85-B-000XX

TABULATION OF BIDS FOR GEORGE WASHINGTON
 MEMORIAL PARKWAY, PROJECT 1A58, CONSISTING OF
 PAVEMENT WIDENING AND OTHER WORK FOR
 ACCELERATION LANE FROM CIA-FHWA FEDERAL AREA AT
 LANGLEY TO NORTHBOUND GWMP IN FAIRFAX COUNTY,
 VIRGINIA. TYPE CODE Y006.

+++++
 + ENGINEER'S +
 + ESTIMATE DATED +
 + APRIL 9, 1985 +
 +++++

FOR OFFICIAL USE ONLY

ITEM NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	AMOUNT
202(3A)	REMOVAL OF BITUMINOUS PAVEMENT(FULL DEPTH)	SQYD	1,400.000\$	7.000\$	9,800.00
202(3F)	REMOVAL OF BITUMINOUS PAVEMENT(MILLING)	SQYD	4,000.000	4.000	16,000.00
202(5B)	REMOVAL OF CONCRETE CURB	LNFT	2,100.000	3.000	6,300.00
203(3)	UNCLASSIFIED EXCAVATION	CUYD	700.000	20.000	14,000.00
204(4F)	EROSION CHECK FOR SOIL EROSION AND POLLUTION CONTROL	LNFT	1,500.000	5.000	7,500.00
304(3F)	CRUSHED AGGREGATE BASE, GRADING B, C, OR D	TON	1,000.000	20.000	20,000.00
403(1B)	HOT BITUMINOUS CONCRETE PAVEMENT, GRADING B	TON	500.000	60.000	30,000.00
403(1D)	HOT BITUMINOUS CONCRETE PAVEMENT, GRADING D	TON	700.000	65.000	45,500.00
601(1)	MOBILIZATION	LPSM			71,564.00
603(21DC)	18-INCH REINFORCED CONCRETE PIPE, CLASS III	LNFT	30.000	50.000	1,500.00
604(2A)	INLETS, TYPE A	EACH	2.000	3,000.000	6,000.00
604(2G)	INLETS, TYPE D1-7A	EACH	5.000	3,000.000	15,000.00
604(6)	INLET, ADJUSTMENT	EACH	4.000	850.000	3,400.00
604(9)	CAPPING INLET	EACH	3.000	200.000	600.00

FOR OFFICIAL USE ONLY

FEDERAL HIGHWAY ADMINISTRATION
 EASTERN DIRECT FEDERAL DIVISION
 ARLINGTON, VIRGINIA
 TABULATION OF BIDS

TABULATION OF BIDS FOR GEORGE WASHINGTON
 MEMORIAL PARKWAY, PROJECT 1A58

+++++
 + ENGINEER'S +
 + ESTIMATE DATED +
 + APRIL 9, 1985 +
 +++++

ITEM NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	AMOUNT
604(21A)	INLET MODIFICATION, TYPE D1-7A	EACH	5.000	1,200.000	6,000.00
605(17A)	4-INCH-PIPE FOR UNDERDRAINS	LNFT	1,000.000	14.000	14,000.00
609(1E)	PORTLAND CEMENT CONCRETE CURB, 16-INCH DEPTH TYPE 2 OR 3	LNFT	800.000	14.000	11,200.00
610(11)	STONE MASONRY GUARDWALL WITH DOUBLE MASONRY FACE	LNFT	1,800.000	150.000	270,000.00
619(17)	LOOSE RIPRAP, CLASS II	TONS	150.000	10.000	1,500.00
624(3A)	FURNISHING AND PLACING TOPSOIL(2-INCH DEPTH)	SGYD	4,500.000	2.000	9,000.00
625(17)	SEEDING (WITH MULCH)	UNIT	20.000	100.000	2,000.00
626(1)	FURNISH AND PLANT TREES AND SHRUBS	LPSM			70,000.00
629(1)	SOLID SODDING	SGYD	4,500.000	6.000	27,000.00
633(4C)	ALUMINUM SIGN PANELS TYPE III REFLECTIVE SHEETING	SGFT	20.000	50.000	1,000.00
634(1)	TRAFFIC MARKINGS, REFLECTORIZED, BROKEN, WHITE OR YELLOW	LNFT	3,000.000	0.500	1,500.00
634(2)	TRAFFIC MARKINGS, REFLECTORIZED, SOLID, WHITE OR YELLOW	LNFT	4,800.000	0.500	2,400.00
635(1)	CONSTRUCTION SIGNS	SGFT	253.000	12.000	3,036.00
635(2B)	BARRICADE, TYPE II	EACH	100.000	140.000	14,000.00
635(2C)	BARRICADE, TYPE III	EACH	5.000	300.000	1,500.00

FOR OFFICIAL USE ONLYFEDERAL HIGHWAY ADMINISTRATION
EASTERN DIRECT FEDERAL DIVISION
ARLINGTON, VIRGINIA
TABULATION OF BIDSTABULATION OF BIDS FOR GEORGE WASHINGTON
MEMORIAL PARKWAY, PROJECT 1A58+++++
+ ENGINEER'S +
+ ESTIMATE DATED +
+ APRIL 9, 1985 +
+++++

ITEM NO.	ITEM	UNIT	QUANTITY	UNIT PRICE	AMOUNT
635(6A)	CONE, TYPE A	EACH	100.000	40.000	4,000.00
635(12)	TEMPORARY CONCRETE BARRIER	LNFT	2,000.000	32.000	64,000.00
635(13)	MOVING TEMPORARY CONCRETE BARRIER	LNFT	750.000	10.000	7,500.00
635(14A)	WARNING LIGHT, TYPE A	EACH	10.000	200.000	2,000.00
635(14C)	WARNING LIGHT, TYPE C	EACH	90.000	200.000	18,000.00
635(16)	FLASHING ARROW BOARD	HOURL	300.000	10.000	3,000.00
635(17)	TEMPORARY TRAFFIC MARKING	LNFT	6,000.000	0.500	3,000.00
635(20)	FLAGGER	HOURL	100.000	12.000	1,200.00
635(27)	IMPACT ATTENUATOR	EACH	1.000	2,000.000	2,000.00
637(3)	COMBINED FIELD OFFICE AND FIELD LABORATORY	EACH	1.000	14,000.000	14,000.00
				\$	800,000.00

SMALL BUSINESS CONCERN:
 SMALL DISADVANTAGED BUSINESS CONCERN:
 WOMAN-OWNED BUSINESS:
 TYPE OF BID GUARANTEE:
 BID CONSIDERED RESPONSIVE:

BIDS OPENED BY:
 BIDS READ BY:

CERTIFIED COMPLETE AND ACCURATE

 DAVID O. WEBER
 ENGINEERING COORDINATOR